

Sep 06, 2018 - 9:26am
M:\2018\18022 HCA RGRH Inpatient Rehab\Drawings\Electrical\E5.01_FLOOR PLANS - SPECIAL SYSTEMS.dwg
crothlauf




RENOVATION LEGEND	
SYMBOL	DESCRIPTION
	EXISTING TO REMAIN "(E)"
	RELOCATED "(R)"
	NEW CONSTRUCTION

SPECIAL SYSTEMS COORDINATION	
THE INTENT OF THIS DRAWING IS TO PROVIDE THE CONTRACTOR WITH AN APPROXIMATE LAYOUT AND ESTIMATION OF THE QUANTITY OF BOXES FOR SPECIAL SYSTEMS DEVICES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE ALL FIRE ALARM & NURSE CALL COMPONENTS, QUANTITIES & LOCATIONS WITH THE OWNER'S PREFERRED VENDORS. CONTRACTOR SHALL UPDATE THEIR BACKBOX/CONDUIT QUANTITIES AFTER COORDINATING WITH VENDORS AND INCLUDE CORRECT QUANTITIES IN BID. REFER TO GENERAL SPECIAL SYSTEMS NOTES.	

GENERAL SPECIAL SYSTEMS NOTES	
1. ALL SPECIAL SYSTEMS BOXES, SLEEVES & CONDUIT ARE PART OF THIS CONTRACT.	
2. PROVIDE BOXES & 1-INCH CONDUIT WITH CONNECTOR & BUSHING TO ACCESSIBLE LOCATION ABOVE THE CEILING. PROVIDE A PULL STRING IN EACH CONDUIT AND TIE OFF PULL STRING ABOVE CEILING. FOR FLOOR OUTLETS, PROVIDE 1-INCH CONDUIT TO ACCESSIBLE LOCATION ABOVE THE CEILING ON THE FLOOR SERVED BY THE OUTLET.	
3. DATA/COMMUNICATION/PHONE & SECURITY/ACCESS CONTROL: CONTRACTOR SHALL ONLY PROVIDE BOXES, SLEEVES & CONDUIT AS DESCRIBED ABOVE IN NOTE 2. CABLING, DEVICES & INSTALLATION ARE OWNER FURNISHED & OWNER INSTALLED AND WILL NOT BE PART OF THIS CONTRACT.	
4. FIRE ALARM & NURSE CALL: CABLING, DEVICES AND INSTALLATION ARE TO BE SUBCONTRACTED (AS PART OF THIS CONTRACT) TO THE OWNER'S PREFERRED SPECIAL SYSTEMS VENDOR. PROVIDE BOXES, SLEEVES AND CONDUIT AS DESCRIBED ABOVE IN NOTE 2. VERIFY AND COORDINATE.	

SPECIAL SYSTEMS SYMBOL LEGEND	
SYMBOL	DESCRIPTION
	COMMUNICATIONS DATA/PHONE OUTLET.
	COMMUNICATIONS TELEVISION OUTLET.
	COMMUNICATIONS SPEAKER.
	COMMUNICATIONS WIRELESS ACCESS POINT.
	FIRE ALARM CONTROL PANEL.
	FIRE ALARM ANNUNCIATOR PANEL.
	FIRE ALARM PULL STATION.
	FIRE ALARM STROBE.
	FIRE ALARM COMBINATION HORN/STROBE.
	FIRE ALARM SMOKE DETECTOR.
	FIRE ALARM DUCT MOUNTED SMOKE DETECTOR.
	FIRE ALARM REMOTE TEST SWITCH.
	FIRE ALARM HEAT DETECTOR.
	FIRE ALARM MAGNETIC DOOR HOLDER.
	NURSE CALL MASTER.
	NURSE CALL TERMINAL CABINET.
	NURSE CALL DOME LIGHT. 1900 BOX WITH SINGLE GANG TRIM & 1" CONDUIT.
	NURSE CALL ZONE LIGHT. 1900 BOX WITH SINGLE GANG TRIM & 1" CONDUIT.
	NURSE CALL SINGLE BED PATIENT STATION. 3-GANG & 1" CONDUIT.
	NURSE CALL CODE BLUE STATION. 1-GANG & 1" CONDUIT.
	NURSE CALL EMERGENCY PULL STATION. 1-GANG & 1" CONDUIT.
	NURSE CALL DUTY STATION. 3-GANG & 1" CONDUIT.
	SECURE ACCESS REQUEST TO EXIT.
	SECURE ACCESS CARD READER.
NOTE: NOT ALL SYMBOLS MAY BE USED.	



HEITKAMP SWIFT

ARCHITECTS

Architecture • Interiors • Planning

1165 BRITTMOORE RD.
HOUSTON, TEXAS 77043
(T) 713.626.4300
(F) 713.626.4301

in association with:

Garner-Fritzsche
ENGINEERING, INC.

8554 Katy Freeway, Suite 101, Houston, TX 77024
713.432.1422 • Fax 713.432.1253
www.garnerfritzsche.com
Texas Reg. No. F-5712
GFE Project No. 18022

bennett
design
group

1165 Brittmoores Rd.
Houston, Texas 77043
p: 713.850.8833 f: 713.850.0383

Rio Grande
REGIONAL HOSPITAL
An HCA Affiliated Hospital

3rd Floor

INPATIENT

REHAB UNIT

FOR INTERIM REVIEW ONLY

THIS DOCUMENT IS RELEASED
FOR THE PURPOSE OF INTERIM
REVIEW ONLY, UNDER THE
AUTHORITY OF:
Name: GREG W. MERCER
P.E. No. 114431
DATE: 09/06/2018
AND IS NOT INTENDED TO
BE USED FOR BIDDING OR
CONSTRUCTION PURPOSES.

REVISIONS		
NO.	ISSUE	DATE
Sheet Information		
DATE		09/06/2018
JOB NUMBER		18302
		TITLE
PARTIAL FLOOR PLAN - SPECIAL SYSTEMS - AREA 1		
SHEET		
E5.01		
ISSUED FOR PRICING ONLY		
Copyright © 2018 Heitkamp Swift Architects		

PARTIAL FLOOR PLAN - SPECIAL SYSTEMS - AREA 1

1/8" = 1'-0"